

# The Oil Report August 2020

Oil the News that's Fit to Print!

Have you heard our podcast? Covering everything from racing to flying to oil change intervals, SlickTalk is your home for all things oil. Available everywhere, including your <u>favorite</u> <u>podcast</u> <u>platform</u>.

Also, if you didn't catch the news, the cost of a sample went up \$2 and is now \$30. If you're a check writer, please note!

## Finishing the RV-12! by Ryan Stark

For those of you who have been reading these newsletters, you'll know that I have been in the process of building a light-sport kit plane made by Van's Aircraft called the RV-12. Last year I <u>chronicled the progress</u> and mentioned that I was getting close to the end. Well, thankfully the end has come, though I have to say it took quite a bit longer than expected.

#### Excitement/Burnout

We moved the project from the garage here at the lab to a hangar out at Fort Wayne International Airport in early July 2019. The days following the move were a time of excitement and hope, though that feeling wouldn't last. My wife and I have been working on this project since the summer of 2016 and we were both kind of getting burned out. However, actually being at the airport and talking with the other owners there helped keep our enthusiasm for the project going. In talking with the other homebuilt owners, it became apparent that even after it's flying, there is always something to work on, but we didn't worry about that much. We still had a lot of work to do just to get ours in the air. This was the part of the building process that's a running joke among homebuilders — 90% done, 90% left to go!



The first engine run!

#### Ironing Out the Details

Soon the prop was installed and the final fitting work on the

cowling was done. We ironed out some bugs in the electronics and communication systems, most of which were mistakes we brought upon ourselves. Before too long, we came to the point where there was nothing left to do in the building instructions.

Next came a thorough checkout of all the systems. Van's provides what they call the production acceptance procedures, which is a very helpful document that tells you how to go through all the systems to make sure they are set up and working properly. It includes things like "Move the control stick to neutral and measure the

right aileron drop, it should be 1/4 to 1/2 inch." Sounds easy enough, until you realize that just about every step requires some type of filling or adjustment on your part.

#### The Fuel Flow Blues

After a few months of work, we got to the fuel flow test. That's exciting because right after that you get to start the angine for the first time. We built the fuel tank

the engine for the first time. We built the fuel tank about a year and a half earlier and up until then, it had not had any fuel in it. I was dreading putting fuel in for the first time, and for good reason, because as soon as I did, it started leaking out of a return line fitting. That was a pretty dark point in the whole process because it meant I had to pull the fuel tank, open it up, fix the leak, and reseal it. Anyone who has ever worked with fuel tank sealant knows this is not fun stuff to work with and it's even less fun to try and clean it off parts. It's also the point at which I realized that I had spent a significant portion of my life building something that would only fly about 120 knots max (with a tailwind) and wouldn't even be able to haul my whole family while doing it. And to further sour my mood, this was mid October and I knew at that point there was no way I'd be able to get it done in 2019.



Back from the first flight!

#### Trying Again

So, after a good pity party and some time off, we got

back to work. The fuel tank was fixed and reinstalled, though by that time it was too cold to get any serious work done at the hangar. That was okay though because it was also time to start the paperwork.

As some of you know, I inherited this project from my father and I can say for sure that the paperwork part would have been what he hated the most. Still, if you keep plugging away, eventually it all comes together. I was able to obtain a N-number (on my second try) and by the time spring rolled around, we were ready to test the fuel flow again and start the engine. As you might imagine I was fairly nervous about this whole process, but the fuel tank held up, the fuel flow test went well, and on May 3, 2020, our Rotax 912 fired up for the first time since it left Austria.

#### But is it Airworthy?

With the motor running and fuel tank sound, I was starting to feel a lot better about this project, though I still had the airworthiness inspection to deal with. This is generally the last step before you can fly and was a big unknown in my mind. It was also a little tough to get scheduled because not only did the FAA switch to a new and confusing online application process, the Indianapolis office had been closed since mid-March due to Covid-19. They were just starting to reopen in mid May when I contacted them, but they were facing a serious back log of work that needed to be processed before they got to me. That basically left me with the choice to either wait until they got time to send someone up (for no charge) or I could contact a DAR (designated airworthiness inspector) and pay to have them take a look. Not wanting to delay this project into 2021, I chose the DAR and scheduled an inspection. Surprisingly enough, the actual inspection was painless and lasted just three hours. At the end I found myself wanting to show the inspector more of my airplane, so he could see the safety wire on the gascolator that I redid three times. Or admire the beautiful fiberglass work on the cowl that took several weeks to sand to perfection.

#### Airborne!

With all the paperwork done and my airworthiness certificate on board, I was finally able to make my first flight on Monday July 13th. It went well, the wings stayed on, and the airplane showed no tendency to do anything crazy. As you can imagine, I was relieved. Now, on to some flight testing, as soon as I can get my transponder to report altitude... ahh the joys of homebuilt ownership.

### **Report of the Month**

The IO-360 engine in this Piper Arrow had a problem. Can you tell what it was? To learn more about where the elements are coming from, click here.

	MI/HR on Oil	30		52					
1	VII/HR on Unit	532	UNIT / LOCATION	481					UNIVER SA L
-	Sample Date	5/31/2020	AVERAGES	1/30/2020	Constant of the local division of the local				AVE RAGES
	Make Up Oil Added	5 qts		9 qts	and the second second			Car Carl	
	17. <sup>1</sup>				1.50	mine	the second second	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
	ALUMINUM	16	19	21			- Aller	ACCORD .	6
	CHROMIUM	7	10	13	18 4		1.1		4
1	RON	26	36	45					28
	COPPER	3	4	5				3. A.	7
1	LEAD	2893	3398	3902				and the second	4462
1	TIN	1	3	4					1
C NH-	MOLYBDENUM	1	1	0	1000				0
1	NICKEL	1	2	2				a second	2
	MANGANESE	0	0	0					0
1	SILVER	0	0	0			1	S. L. M. S. C.	0
	TITANIUM	0	0	0					0
	POTASSIUM	1	1	0	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1		Но	les	1
	BORON	0	1	1	1.48				1
	SILICON	15	22	29	100				5
	SODIUM	1	1	1					1
(	CALCIUM	52	50	48					17
1	MAGNESIUM	2	4	5					3
F	PHOSPHORUS	186	117	48					536
	ZINC	4	7	9					4
8	BARIUM	0	0	0					0
	ĥ	3. Až	Values					1124	
			Should Be*		2		22	125	
	SUS Viscosity @ 210°F	94.2	86-105	76.7					
	cSt Viscosity@100°C	18.99	17.0-21.8	14.68	_				
	Flashpoint in °F	470	>430	455					
I	Fuel %	<0.5	<1.0	<0.5		-			
	Antifreeze %	-		-					
	Nater %	0.0	0.0	0.0					
2	nsolubles %	0.2	<0.6	0.3					
•	TBN								
	TAN								
1	SO Code								

The first sample was the owner's initial analysis after he bought the airplane. That sample indicated high silicon. he changed the air filter element and found some leaks in the filter housing, repairing everything he could find. That helped. But when he did the second sample, silicon had improved, but it was still elevated. And we were still seeing metal. At that point the owner pulled the SCEET air duct off. It's not easy to see in the picture, but the duct had many holes in the walls. That should take care of the lingering dirt contamination issues, and help improve wear quite a bit.